

# Construction Systems Comparison

Factor	Green Precast Modular	Blockwork	Conventional Panels	Lightweight Steel Frame
<b>Build Concept</b>	<ul style="list-style-type: none"> <li>A single trade and subcontract package</li> <li>Cast complete rooms in one piece and install with a single lift</li> <li>Sub-terrain structures</li> </ul>	<ul style="list-style-type: none"> <li>Requires separate structures of beams, columns and floor system using precast</li> <li>Wall in-fills need more jointing detail</li> <li>Must use separate floor system for multi-level</li> </ul>	<ul style="list-style-type: none"> <li>Flat elements cast on flat table and installed individually and require numerous joints, brackets and grouting</li> </ul>	<ul style="list-style-type: none"> <li>Steel lightweight frame, clad with gypsum or cement sheet. Many joints to flush fill.</li> <li>Requires top/bottom elements install first due to tolerances or structure complete for site measure.</li> </ul>
<b>Factory Production</b>	<ul style="list-style-type: none"> <li>Monolithic cast of wall units and ceiling, to between the equivalent of 5 and 14 flat panels</li> <li>No brackets, props or vertical joints required</li> <li>Customizable for penetrations and openings</li> <li>Repetitious production of a module</li> </ul>	<ul style="list-style-type: none"> <li>More on-site trades: reinforcement, brick or block laying and rendering</li> <li>On-site labour intensive</li> <li>Load-bearing needs to be steel and concrete reinforcement</li> <li>Concrete pump and untidy</li> </ul>	<ul style="list-style-type: none"> <li>Larger factory area for equivalent production and many more vertical joints</li> </ul>	<ul style="list-style-type: none"> <li>Can be panelised but needs to be fixed prior to final cladding.</li> <li>Access issues for larger premade elements.</li> <li>Many joints to finish</li> </ul>
<b>Insulation</b>	<ul style="list-style-type: none"> <li>Closed joints reducing locations for air transfer</li> <li>Mould internal foam layer sandwich panel (200-210mm)</li> <li>External UV reflective coating (up to 100%), available in 45 colours</li> </ul>	<ul style="list-style-type: none"> <li>N/A</li> </ul>	<ul style="list-style-type: none"> <li>Must be cast in foam, walls have a perimeter boarder not containing insulation</li> <li>Many vertical joints</li> <li>Cast in foam layer does not extend to full area of panel</li> </ul>	<ul style="list-style-type: none"> <li>Can be placed in wall cavity, or post fixed.</li> </ul>
<b>Wastage</b>	<ul style="list-style-type: none"> <li>Walls and roof act together structurally minimizing the volume of concrete, steel and reinforcing bars leading to less wastage</li> </ul>	<ul style="list-style-type: none"> <li>Excessive site wastage, cleanup, disposal: cutting of bricks and blocks, pallets, mortar, sand piles, hoses and water</li> </ul>	<ul style="list-style-type: none"> <li>Minimum 2 layers of reinforcing for insulated walls</li> <li>Requires extra 12m of vertical jointing per room</li> </ul>	<ul style="list-style-type: none"> <li>Room sizes not always as per standard steel &amp; cladding sheet lengths.</li> </ul>
<b>Finishes</b>	<ul style="list-style-type: none"> <li>Internal and external paint can be applied in the production process</li> </ul>	<ul style="list-style-type: none"> <li>Only achieved by site application, increased labour cost and inferior accuracy</li> <li>Coloured bricks available but generally need to apply another finish or lining</li> </ul>	<ul style="list-style-type: none"> <li>Factory painting not possible due to multiple joints</li> <li>Colour variation as panels are poured separately</li> <li>More visible joints</li> </ul>	<ul style="list-style-type: none"> <li>Much flushing and filling of joints on site.</li> <li>Pre-painting not usually possible due to multiple joints.</li> </ul>
<b>Labour</b>	<ul style="list-style-type: none"> <li>Hydraulic mould requires 8 men to operate up to 80m<sup>2</sup> per 12 hours</li> <li>Installation requires 3 people</li> </ul>	<ul style="list-style-type: none"> <li>Labour intensive</li> <li>Requires more site amenities, supervision, temporary services and scaffolding</li> </ul>	<ul style="list-style-type: none"> <li>Each panel requires 2 man-days (≈10 man-days for 5 panels)</li> </ul>	<ul style="list-style-type: none"> <li>Labour intensive to assemble as many pieces and several different materials required to complete.</li> </ul>

Factor	Green Precast Modular	Blockwork	Conventional Panels	Lightweight
<b>Installation</b>	<ul style="list-style-type: none"> <li>A single lift</li> <li>No propping or levelling</li> <li>Minimal site fittings, brackets and dowels</li> <li>Solid working platform immediately available for subsequent levels</li> <li>Erect 4-5 levels in one day</li> <li>Greater accuracy, monolithic construction reduces bracket and joint costs ≈\$100 per room</li> </ul>	<ul style="list-style-type: none"> <li>Slow</li> <li>Labour intensive</li> <li>Greater overhead costs</li> </ul>	<ul style="list-style-type: none"> <li>Multiple small lifts causes delays, 2 levels per day max</li> <li>5 crane movements to install 1 panel</li> <li>Individual propping and levelling</li> <li>Less accuracy with accumulating errors</li> <li>No immediate working platform until all jointing is completed</li> </ul>	<ul style="list-style-type: none"> <li>Multiple small lifts, 2 levels per day max.</li> <li>Individual piece propping &amp; leveling.</li> <li>Post installation access is difficult until floors &amp; other structural elements complete &amp; clad.</li> </ul>
<b>Transport and lifting</b>	<ul style="list-style-type: none"> <li>1 crane to extract and place for yard and site</li> </ul>	<ul style="list-style-type: none"> <li>Extensive scaffolding, materials hoist and safety provisions</li> </ul>	<ul style="list-style-type: none"> <li>Need approximately 8 cranes on site</li> </ul>	<ul style="list-style-type: none"> <li>Can be flat packed. Generally lightweight.</li> <li>Require site storage areas.</li> <li>Difficult to “load” building until all bracing done.</li> </ul>
<b>Services</b>	<ul style="list-style-type: none"> <li>Windows and door frames, electrical and plumbing conduits built into mould</li> <li>Can cast holes in roof slabs for vertical plumbing service running from top to bottom of building</li> </ul>	<ul style="list-style-type: none"> <li>Must be progressively manually built in or chased in later</li> </ul>	<ul style="list-style-type: none"> <li>Impractical to factory install windows</li> <li>Corner electrical joining impossible</li> <li>Plumbing service holes more difficult</li> </ul>	<ul style="list-style-type: none"> <li>Impractical to factory install windows. MEP coordination extremely difficult and practically better to do on site.</li> </ul>
<b>Hydronic cooling/heating</b>	<ul style="list-style-type: none"> <li>Pipes can be cast into floor for efficient cooling/heating</li> </ul>	<ul style="list-style-type: none"> <li>Not possible</li> </ul>	<ul style="list-style-type: none"> <li>Difficult/impossible to do with hollow core planks</li> </ul>	<ul style="list-style-type: none"> <li>Coordination of connections through all the elements generally make it more practical to do insitu once installed.</li> </ul>
<b>Safety</b>	<ul style="list-style-type: none"> <li>Modern lifting techniques</li> <li>Safe working platforms</li> <li>Limited access to external surface required</li> </ul>	<ul style="list-style-type: none"> <li>Excessive site labour with potentially high injury risk</li> <li>Loose power leads, hoses and scaffolding creates safety risks</li> </ul>	<ul style="list-style-type: none"> <li>Installation requires temporary phase (propping) with added safety requirement</li> </ul>	<ul style="list-style-type: none"> <li>Significant site labour with potentially high injury risk</li> <li>Loose power leads, hoses and scaffolding creates safety risks</li> </ul>